



SITE LOCATION
E:460727 N:099467

- NOTES**
- DO NOT SCALE FROM THIS DRAWING
 - ALL DIMENSIONS IN METRES UNLESS OTHERWISE STATED
 - THIS DRAWING IS TO BE REPRODUCED IN COLOURS

- KEY**
- SITE CLEARANCE**
- x — EXISTING KERB TO BE TAKEN UP AND DISPOSED OFF SITE (29m)
 - BREAK OUT EXISTING FOOTWAY TO FORMATION LEVEL PLUS 120mm (7.60m²)
 - BREAK OUT EXISTING FOOTWAY TO A DEPTH OF 20mm FOR FOOTWAY INLAY RESURFACING (19.50m²)
 - TAKE UP AND STORE OFF SITE PLASTIC KEEP RIGHT BOLLARD (01un.)
- PROPOSED**
- PROPOSED TYPE PC1 PRECAST CONCRETE KERB TO STANDARD DETAIL HCC10/C/010 (17.20m)
 - PROPOSED TYPE 1A FULL DEPTH FOOTWAY CONSTRUCTION TO STANDARD DETAIL HCC10/C/045 (7.60m²)
 - PROPOSED TYPE 1A FOOTWAY INLAY RESURFACING (19.50m²)
 - RELOCATE BOLLARD (01 un.)

© CROWN COPYRIGHT AND DATABASE RIGHTS 2019
ORDNANCE SURVEY 100019180

CLIENT HAMPSHIRE COUNTY COUNCIL ECONOMY, TRANSPORT AND ENVIRONMENT DEPARTMENT STRATEGIC TRANSPORT				CONSULTANT STUART JARVIS BSc DipTP FCIHT MRTPI: DIRECTOR OF ECONOMY, TRANSPORT & ENVIRONMENT				DESIGNER GC SCALE @ A3 1:200 DATE 07.01.2019 CHECKED PJ PJ SHEET NUMBER 1 OF 1 APPROVED JR				SCHEME GOSPORT & FAREHAM LOCAL CYCLING AND WALKING INFRASTRUCTURE PLAN JOB No. R.J507361				DRAWING TITLE PRELIMINARY DESIGN SECTION D <small>HCC CAD PLOT: 25/12/2019 16:22:13</small>			
SZ	PO1	FIT FOR INFORMATION		07.01.2019															
SUIT	REV	AMENDMENTS		DATE	CAD	CHKD	APPD												