



PROPOSED WORKS -

Install 12m pontoon from north end of hoist dock, connecting to existing pontoon.

The purpose is to assist launching of vessels (including dry stack) as existing layout is restrictive operationally.

No piling is proposed and it is anticipated that MMO Exemption 25A will apply with Harbour Works Consent.

A support guide will be installed on the end of the hoist dock.

The pontoon will arrive by road and assembled in the boatyard. It will then be craned into position.

The use of marine plant is not envisaged.

Installation would be completed within 2 days.

NOTES

1. Grid shown is OSGB National Grid

Original LTS print only with Red Stamp

21:03:19	Rev A - MLW mark added
09:02:19	First Issue

Date	Issue
------	-------

LYMINGTON TECHNICAL SERVICES LTD

CLIENT
JOHN WILLMENT MARINE LTD

SITE
UNIVERSAL MARINA

TITLE
HOIST DOCK LANDING PONTOON

SCALE AS SHOWN @ A1

DRAWN <i>P. Tosswell</i>	DATE <i>Feb 2019</i>
-----------------------------	-------------------------

DRG No 10584/44B